



FOREST DEVELOPMENT PROJECT

CORRIDOR 19 BRIDGES OVER LANGDON BROOK AND UNNAMED TRIBUTARY



White Mountain National Forest
 Saco Ranger District
 Chatham, Carroll County, NH

FINAL DESIGN DRAWINGS

Structure #09220000035580, McDonough Brook 1
 Latitude: 44.15719, Longitude: -71.03632
 Structure #09220000035579, McDonough Brook 2
 Latitude: 44.15779, Longitude: -71.03698

FR 244


May 30, 2025



SHEET	NAME	TITLE
1	C0.01	COVER SHEET
2	C0.02	GENERAL NOTES
3	C1.11	LANGDON BROOK ROADWAY PLAN & PROFILE
4	C1.12	TRIBUTARY ROADWAY PLAN & PROFILE
5	C3.01	TYPICAL ROADWAY SECTION
6	C3.20	ROADWAY SECTIONS 0+80 - 3+90
7	C3.21	ROADWAY SECTIONS 4+00 - 6+00
8	S1.01	LANGDON BROOK BRIDGE PLAN & ELEVATION
9	S1.02	TRIBUTARY BRIDGE PLAN & ELEVATION
10	S1.21	LANGDON BROOK SUBSTRUCTURE PLAN & SURVEY LAYOUT
11	S1.22	TRIBUTARY SUBSTRUCTURE PLAN & SURVEY LAYOUT
12	S5.11	SUBSTRUCTURE SECTION & ELEVATION

Supplemental Plans

1	V1.01	EXISTING - FEATURES PLAN
2	W0.01	ENVIRONMENTAL RESOURCE NOTES
3	W1.11	LANGDON BROOK PLAN & PROFILE
4	W1.12	TRIBUTARY PLAN & PROFILE
5	W1.21	LANGDON BROOK EROSION & SEDIMENT CONTROL PLAN
6	W1.22	TRIBUTARY EROSION & SEDIMENT CONTROL PLAN
7	W3.01	TYPICAL CHANNEL SECTIONS
8	W3.11	LANGDON BROOK CHANNEL SECTIONS
9	W3.12	TRIBUTARY CHANNEL SECTIONS
10	W5.11	EROSION & SEDIMENT CONTROL DETAILS




DISTRICT RANGER - SACO RANGER DISTRICT	DATE
FOREST ENGINEER	DATE
FOREST SUPERVISOR	DATE
REGIONAL BRIDGE PROGRAM MANAGER - EASTERN REGION	DATE
DIRECTOR OF ENGINEERING - EASTERN REGION	DATE


P:\Users\202304\1\Projects\2023\04\1\CD\1\Cover Sheet.dwg, Cover Sheet, 0/20/25 8:52:19 AM, jmasabug

Line Table: Alignments				
Line #	Length	Direction	Start Point	End Point
L1	48.20	N76° 04' 26.09"W	(N=604555.52 E=1149825.52)	(N=604567.12 E=1149778.74)
L2	82.00	N41° 09' 48.98"W	(N=604592.41 E=1149732.53)	(N=604654.15 E=1149678.56)
L3	110.94	N38° 58' 21.45"W	(N=604723.12 E=1149621.22)	(N=604809.37 E=1149551.45)
L4	52.00	N30° 54' 33.18"W	(N=604853.12 E=1149519.64)	(N=604897.74 E=1149492.93)

Curve Table: Alignments						
Curve #	Radius	Length	Chord Direction	Chord Length	Start Point	End Point
C1	99.85	27.44	N68° 15' 32.19"W	27.35	(N=604545.39 E=1149850.93)	(N=604555.52 E=1149825.52)
C2	132.48	32.43	N67° 52' 41.48"W	32.35	(N=604567.12 E=1149778.74)	(N=604579.30 E=1149748.77)
C3	75.20	20.94	N51° 05' 03.87"W	20.87	(N=604579.30 E=1149748.77)	(N=604592.41 E=1149732.53)
C4	2705.15	89.70	N39° 44' 06.93"W	89.70	(N=604654.15 E=1149678.56)	(N=604723.12 E=1149621.22)
C5	417.28	54.13	N36° 01' 00.61"W	54.09	(N=604809.37 E=1149551.45)	(N=604853.12 E=1149519.64)
C6	717.34	89.87	N27° 06' 50.58"W	89.81	(N=604897.74 E=1149492.93)	(N=604977.68 E=1149451.99)



Plan
Scale: 1" = 10'



Profile
Scale: 1" = 10'

General Notes

4		
3		
2		
1		
No.	Revision/Issue	Date

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE

R-9

Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District

HEB ENGINEERS HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebengineers.com
Office (603) 356-6936

Drawing Title
Langdon Brook Roadway Plan & Profile


Designed/Drawn	COB	Project	2023-004
Checked	JKM	Drawing No.	C1.11
CAD File No.	-		
Date	05/30/2025		
Scale	1"=10'		

Line Table: Alignments


Line #	Length	Direction	Start Point	End Point
L1	48.20	N76° 04' 26.09"W	(N=604555.52 E=1149825.52)	(N=604567.12 E=1149778.74)
L2	82.00	N41° 09' 48.98"W	(N=604592.41 E=1149732.53)	(N=604654.15 E=1149678.56)
L3	110.94	N38° 58' 21.45"W	(N=604723.12 E=1149621.22)	(N=604809.37 E=1149551.45)
L4	52.00	N30° 54' 33.18"W	(N=604853.12 E=1149519.64)	(N=604897.74 E=1149492.93)

Curve Table: Alignments

Curve #	Radius	Length	Chord Direction	Chord Length	Start Point	End Point
C1	99.85	27.44	N68° 15' 32.19"W	27.35	(N=604545.39 E=1149850.93)	(N=604555.52 E=1149825.52)
C2	132.48	32.43	N67° 52' 41.48"W	32.35	(N=604567.12 E=1149778.74)	(N=604579.30 E=1149748.77)
C3	75.20	20.94	N51° 05' 03.87"W	20.87	(N=604579.30 E=1149748.77)	(N=604592.41 E=1149732.53)
C4	2705.15	89.70	N39° 44' 06.93"W	89.70	(N=604654.15 E=1149678.56)	(N=604723.12 E=1149621.22)
C5	417.28	54.13	N36° 01' 00.61"W	54.09	(N=604809.37 E=1149551.45)	(N=604853.12 E=1149519.64)
C6	717.34	89.87	N27° 06' 50.58"W	89.81	(N=604897.74 E=1149492.93)	(N=604977.68 E=1149451.99)




Plan
Scale: 1" = 10'



Profile
Scale: 1" = 10'

General Notes



No.	Revision/Issue	Date
4		
3		
2		
1		

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE

R-9



Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District

HEB ENGINEERS


HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebengineers.com
Office: (603) 356-6936

Drawing Title
Tributary Roadway Plan & Profile


Designed/Drawn	COB	Project	2023-004
Checked	JKM	Drawing No.	C1.12
CAD File No.	-		
Date	05/30/2025		
Scale	1"=10'		




Station 4+70.00




Station 5+50.00




Station 4+60.00




Station 5+40.00




Station 4+50.00




Station 5+30.00



Station 4+40.00




Station 5+20.00




Station 6+00.00




Station 4+30.00




Station 5+10.00




Station 5+90.00




Station 4+20.00




Station 5+00.00




Station 5+80.00




Station 4+10.00




Station 4+90.00




Station 5+70.00



Station 4+00.00



Station 4+80.00



Station 5+60.00

4		
3		
2		
1		
No.	Revision/Issue	Date

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE

R-9


Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District

HEB ENGINEERS HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebengineers.com
Office: (603) 356-6936

Drawing Title
Roadway Sections 4+00 - 6+00


Designed/Drawn	COB	Project	2023-004
Checked	JKM	Drawing No.	C3.21
CAD File No.			
Date	05/30/2025		
Scale	1"=10'		

P:\Users\j202304\OneDrive\Documents\19_Corridor_19_Bridges\Drawings\Roadway Sections.dwg, Roadway Sections.dwg, 5/30/2025 8:31:31 AM, j202304




Langdon Brook Substructure Plan
Scale: 1/4" = 1'-0"

Working Point	Easting	Northing
A	1149740.243	604601.799
B	1149731.220	604593.914
C	1149722.166	604586.011
D	1149695.485	604652.991
E	1149686.457	604645.099
F	1149677.416	604637.195



Langdon Brook Survey Layout
Scale: 1/4" = 1'-0"

General Notes



No.	Revision/Issue	Date
4		
3		
2		
1		

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE




R-9

Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District


HEB ENGINEERS HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebengineers.com
Office: (603) 356-8936

Drawing Title
**Langdon Brook Substructure Plan
& Survey Layout**

Designed/Drawn COB	Project 2023-004
Checked JKM	Drawing No.
CAD File No. -	S1.21
Date 05/30/2025	
Scale 1/4"=1'-0"	




A Typical Substructure Section
Scale: 3/4" = 1'-0"



B Typical Substructure Elevation
Scale: 1/2" = 1'-0"

General Notes



4		
3		
2		
1		
No.	Revision/Issue	Date

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE



R-9


Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District

HEB ENGINEERS HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebengineers.com
Office: (603) 356-6936

Drawing Title
Substructure Section & Elevation

Designed/Drawn COB	Project 2023-004
Checked JKM	Drawing No.
CAD File No.	S5.11
Date 05/30/2025	
Scale AS NOTED	

Point #	Description	Northing	Easting	Elevation
3	MAGSPIKE	604606.07	1149719.23	831.19
4	MAGSPIKE	604859.84	1149512.42	833.01
5	MAGSPIKE	604591.02	1149686.28	827.12
10	MAGSPIKE	604967.96	1149452.07	838.20



General Notes

Survey Notes:

1. Site features and topography are per field surveying performed June 2023, under the direct supervision of Seth E. Burnell, LLS #985; using a Leica TS16 robotic total station and Leica GS18i GNSS receivers; and conforming with the technical standards for topographic surveys per the NH Code of Administrative Rules of the Board of Licensure for Land Surveyors.
2. Orientation is grid. Coordinate grid is NH State Plane Coordinate System NAD83 datum, established with GPS observations tied to the NGS CORS network.
3. Contour interval = 2 ft. Vertical datum is NAVD83, established with GPS observations tied to OPUS.
4. Jurisdictional wetlands shown were delineated on May 18, 2023 by North Country Soil Services (Gregory W. Howard, CWS #778) and surveyed by HEB per Note 1.

Legend

- Major contour
- Minor contour
- Edge of Water
- Stone wall
- Vegetation line
- Edge of gravel
- Delineated wetland
- Boulder
- Proposed 1% AEP Flood Elevation

No.	Revision/Issue	Date
4		
3		
2		
1		

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE



R-9

Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District



HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebengineers.com
Office (603) 356-6936

Drawing Title
Existing-Features Plan

Designed/Drawn	DWI/TRC	Project	2023-004
Checked	JLT	Drawing No.	V1.01
CAD File No.			
Date	12/03/2024		
Scale	1" = 20'		

U.S. Fish and Wildlife Service Wetland Classifications:



PFO4E Palustrine, Forested, Needle-Leaved Evergreen, Seasonally Flooded/Saturated
R2UB1F Riverine, Upper Perennial, Unconsolidated Bottom, Cobble-Gravel, Semipermanently Flooded

Wetland Delineation Certification:

These wetland delineations are a representation of field data collected on May 18, 2023 by Gregory W. Howard, CWS of North Country Soil Services. The delineated wetland areas meet the criteria for freshwater wetlands as noted in the New Hampshire RSA 482-A:2 (X) "Freshwater Wetlands" meaning an area that is inundated or saturated by surface water or groundwater at a frequency and duration sufficient to support, and which under normal circumstances does support, a prevalence of vegetation typically adapted for life in saturated soil conditions. The wetland delineations were conducted in accordance with NH Code of Administrative Rules CHAPTER Env-Wt 400, PART Env-Wt 406, SECTION Env-Wt 406.02 "Delineation of Wetland Boundaries" effective December 15, 2019, utilizing the Corps of Engineers Wetlands Delineation Manual, January 1987, Technical Report Y-87-1 and the Regional Supplement to the Corps of Engineers Wetlands Delineation Manual: Northcentral and Northeast Region, January 2012.

The wetland delineations shown on this plan are based on my best knowledge and opinion thereof as of the date of this mapping.

12/16/2024
Date
Gregory W. Howard, Certified Wetland Scientist #078



Water Diversion Notes:

- All items covered under the applicable section of the New Hampshire Department of Transportation (NHDOT) Standard Specifications shall be designed by a Professional Engineer, licensed in the State of New Hampshire. The Contractor shall submit stamped working drawings and calculations for review and documentation in accordance with the Contract.
- Water diversion and a clean water bypass are required to generate dry working conditions by means of diverting stream flow around excavation areas. Water diversion structures and clean water bypasses shall be designed and constructed to accommodate the 50 percent recurrence storm event. Water diversion shall be watertight, so as to direct all stream flow through the clean water bypass and prevent flow into excavation areas.
- It may be possible to use a cofferdam, such as a sandbag dike or sheet piling, in lieu of a water diversion structure and clean water bypass as a means of maintaining flow through a partial channel area during excavation. If a cofferdam is used, it is subsidiary to the water diversion structure item.
- Water diversion shall be maintained until channel restoration, including installation of riprap and natural streambed material to grades shown on plans, has progressed to a point such that the channel is capable of maintaining a flow equivalent to the water diversion design storm event.
- The water diversion structure design shall account for the effects of unbalanced earth pressure and construction equipment on the water diversion structure stability.
- Pre-excavation of cobbles and boulders may be required prior to placing steel sheeting. During excavation the Contractor shall disturb the area as little as possible and use necessary precautions to minimize the impacts to the channel. All costs included in the pay item.
- The Contractor should be prepared to perform any subsurface investigations needed for the water diversion structure design. All costs associated with the completion of subsurface investigations, redesign, or reinstallation of water diversion structures due to subsurface conditions encountered during installation that are different from what the water diversion structure designer assumed and/or interpreted from the available subsurface information, shall be subsidiary to the associated water diversion structure item.

Dewatering Notes:

- Control of water within the bridge and wingwall excavation shall be conducted in accordance with the applicable specifications in the Contract, and paid under the associated bridge excavation item. Pumping areas shall be located outside the footing support limits and properly filtered to prevent the pumping of fines.
- Any foundation soil weakened as a result of insufficient care taken in maintaining a dewatered condition shall be removed and replaced with structural fill at the expense of the Contractor.
- Dewatering shall be continuous until substructures are backfilled to the elevations of the surrounding water table, unless noted otherwise.
- All means and methods associated with handling water during construction of foundations shall be located within the limits of work shown on the Wetlands Permit approved for the project, and are subsidiary to the bridge excavation item.

Natural Streambed Material Notes:

- The intent is to stockpile excavated natural streambed material during bridge removal and regrading. The amount of stockpiled material is expected to be less than what is needed for stream restoration, and additional material will likely need to be imported. Material used in restoration should be representative of the up and down stream conditions. Surface roughness, permeability, and particle-size and distribution should all be addressed as part of this work.
- Contractor shall provide samples for Owner's Representative approval for any imported material prior to installation. All costs for stockpiling, importing, and placement of this material are included in the pay item.
- VOIDS of the cobbles and boulders shall be washed in with well-graded rounded stones, sand, and fines to prevent subsurface flow.
- Contractor shall place the natural streambed material in lifts with a thickness of less than 1½ times the maximum dimension of the rocks. The material shall be placed using methods that do not cause segregation or damage to the surface below. Individual rocks shall be placed or rearranged using methods to obtain a compact, low permeability material. Voids shall be filled in prior to placing the next lift.

Critical Erosion Areas:

Temporary seeding and/or mulching shall be used to protect exposed critical areas during construction. The following areas are particularly susceptible to erosion and shall receive extra attention when being inspected and maintained:

- The larger cut and fill areas along the road and driveways.
- Areas not worked or not to be worked for 3 weeks.
- Areas of concentrated flow such as the ditches, swales, and toe of uphill facing slopes.
- Stormwater ponds and level spreaders.

Winter Construction Requirements:

The primary intent of the erosion control requirements and the construction sequence is to stage the project in a manner that will minimize the potential for erosion and the potential negative effects associated therewith. The Engineer shall be contacted and the plan shall be amended if the intent is not being achieved.

- After October 15th, incomplete parking areas where active construction has stopped for the winter shall be protected with a minimum 3-inch layer of base course gravels.
- The area of exposed unstabilized soil shall be limited to one (1) acre.
- Areas with slope of less than 15 percent which do not exhibit 85 percent vegetative growth by October 15th shall be seeded and covered with 3 to 4 tons of hay or straw mulch per acre and anchored with netting or tackifier. All stabilization shall be completed within a day of establishing final grade or that will exist for more than 5 days.
- Areas with slope greater than 15 percent which do not exhibit 85 percent vegetative growth by October 15th shall be seeded and covered with erosion control blanket. All stabilization shall be completed within a day of establishing final grade or that will exist for more than 5 days.
- All ditches or swales which do not exhibit a minimum of 85 percent vegetative growth by October 15th or which are disturbed after October 15th shall be stabilized temporarily with stone or erosion control blankets.
- Installation of anchored hay mulch or erosion control mix shall not occur over snow of greater than 1-inch in depth.
- Installation of erosion control blankets shall not occur over snow greater than 1-inch in depth or on frozen ground.

Construction Equipment Notes:

- Precautions shall be taken within riparian areas to limit unnecessary removal of vegetation for construction access.
- Construction equipment shall be inspected daily for leaking fuel, oil, and hydraulic fluid prior to working near surface waters or wetlands.
- Faulty equipment shall be repaired prior to working near jurisdictional areas.
- The Contractor shall have appropriate oil spill kits on site and readily accessible at all times during construction and each operator shall be trained in its use.

General Erosion-Control Requirements:

The primary intent of the erosion-control requirements and the construction sequence is to stage the project in a manner that will minimize the potential for erosion and sediment and the potential negative effects associated therewith. The Contract Administrator shall be contacted and the plan shall be amended if the intent is not being achieved.

Realizing there is more than one method of achieving the intent, the Contractor may submit an alternate erosion-control plan to the Contract Administrator for consideration. The alternate plan may be implemented if, in the opinion of the Engineer, it will achieve the intent and it is in compliance with the associated permits.

- Erosion-Control Definitions:
 - "Strip topsoil": Excavate topsoil, screen, and stockpile.
 - "Seed(ing)": Adjust pH, apply fertilizer, sow the seed mixture, apply mulch (or erosion-control matting), apply tackifier.
 - "Stabilize(d)": Apply treatment that will minimize erosion when subject to normal rainfall and wind events.
 - "Significant rainfall event": More than ½ inch of rain.
- Install all erosion-control measures prior to earthwork operation and maintain all erosion-control measures and seeded embankments during construction. Erosion-control shall be removed only upon the establishment of all vegetated areas.
- All drainage structure inlets shall be protected using inlet protection or catch basin inserts.
- Erosion-control measures shall be implemented complying with Best Management Practices (BMPs) of the "Stormwater Management and Erosion-and Sediment-Control Handbook for Urban and Developing Areas in New Hampshire" by the NHDES, USDA SCS, and Grafton County Conservation District, latest edition.
- Do not disturb areas outside the limits of proposed work. Areas disturbed by the Contractor's operations shall be restored to their original condition at the Contractor's expense. All areas disturbed during construction not covered with buildings, structures, or pavement shall receive 4 inches of loam and seed.
- The downhill side of all stockpiles shall be encircled with silt fence.
- All ditches, swales, and other areas of concentrated flow shall be stabilized prior to directing flow to them. Catch basin inserts to be installed on all catch basins until the project is fully established.
- Before weekends, and if a significant rainfall event is anticipated during the construction of the cut/fill embankments, a temporary berm shall be constructed along the top of the fill embankments, and temporary slope drains (pipes) with temporary stone outlet aprons shall be installed at the base of the slopes.
- The maximum time that any disturbed areas shall be left unstabilized shall be 14 days.
- The smallest practical area shall be disturbed to complete the required construction, but no more than five (5) acres at any one time.
- All cut and fill slopes shall be seeded and mulched within 72 hours after their construction.
- Lot disturbance, other than that shown on the approved plans, shall not commence until after the roadway and the associated drainage is complete and stable.
- An area shall be considered stable if one of the following has occurred:
 - A. Base course gravels have been installed in areas to be paved;
 - B. A minimum of 85 percent vegetated growth has been established;
 - C. A minimum of 3 inches of non-erosive material such as stone or riprap has been installed; or
 - D. Erosion-control blankets have been properly installed.
- Throughout the construction period, all erosion-control measures shall be inspected at the end of each week and before anticipated significant rainfall events and repaired, if deficient. Extra attention shall be given to the critical areas listed separately.
- All erosion-control measures shall be inspected weekly and after every ½ inch or greater rainfall within a 24 hour period.
- All roadways/parking areas and cut and fill slopes shall be stabilized within 72 hours of achieving finished grade.

Seeding Notes:

- Seed mixture: Prior to construction, submit certification from seed supplier that the mixture complies with the requirements. Include the requirements on the certification.
- Prepare subsoil by eliminating uneven areas; removing foreign materials, weeds, and other undesirable plants and their roots; scarifying subsoil to a depth of 3 inches.
- Spread loam to yield a minimum depth of 4 inches after rolling. Rake smooth to remove stones and roots. Loam shall consist of loose friable topsoil with no admixture of refuse or material toxic to plant growth. Loam shall be generally free from stones, lumps, stumps, subsoil, roots, and weeds or similar objects larger than 2 inches in greatest diameter. The term as used herein shall mean that portion of the soil profile defined technically as the "A" horizon by the Soil Science Society of America. The minimum and maximum pH value shall be from 5.5 to 7.6. Loam shall contain a minimum of 3 percent and a maximum of 10 percent of organic matter as determined by loss by ignition. Not more than 85 percent shall pass a No. 200 sieve as determined by the wash test in accordance with ASTM D 1140. In no instance shall more than 20 percent of that material passing the No. 4 sieve consist of clay size particles.
- Apply agricultural limestone at a rate of 100 pounds per 1,000 square foot.
- Apply commercial grade 10-10-10 fertilizer at a rate of 10 pounds per 1,000 square foot.
- Sow uniformly with last year's crop of the local natural resource conservation service's "conservation mix" at a rate of ½ pound per 1,000 square foot. Mixture is to have a germination rate of not less than 80 percent and a purity of not less than 85 percent.
- Roll seeded area with hand roller.
- Mulch with seedless hay, oak, or straw mulch at a rate of 2 bales per 1000 square foot.
- All ditches shall receive erosion-control matting.

Temporary:

- Bedding: Remove stones and trash that will interfere with seeding the area. Where feasible, till the soil to a depth of about 3 inches to prepare a seedbed and mix fertilizer into the soil. The seedbed should be left in a firm and smooth condition. The last tillage operation should be performed across the slope wherever practical.
- Fertilizers: Fertilizer should be uniformly spread over the area prior to being incorporated into the soil. A minimum of 300 pounds per acre (7 pounds per 1,000 square foot) of 10-10-10 fertilizer, or its equivalent, should be applied.
- Where it is impracticable to incorporate fertilizer and seed into moist soil, the seeded area should be mulched to facilitate germination.
- Seed Mixture: Use any of the following:

Species	Per Acre	Per 1,000 sf.	Dates	Depth
Winter Rye	112 lbs	2.5 lbs	8/15-9/5	1 inch
Oats	80 lbs	2.0 lbs	Spring-5/15	1 inch
Annual Ryegrass	40 lbs	1.0 lb	4/15-9/15	½ inch
Perennial Ryegrass	30 lbs	0.7 lbs	4/1-8/1 or 8/15-9/15	½ inch
- Maintenance: If seeding fails to grow, it may need to be re-established to provide adequate erosion control. If weeds become a problem, they may need to be controlled by mowing.

Construction Sequence:




The New Hampshire Department of Environmental Services (NHDES) requires that certain steps be taken in order to minimize the erosion of soil within the limits of work. These measures are integral to the successful restoration of the project site. Listed below is a potential construction sequence that would achieve this goal. The specific means and methods are to be determined by the Contractor, but must meet the requirements of the approved Wetlands Permit and supporting Contract Documents. Contractor's proposed construction sequence shall be approved by Contract Administrator prior to construction.

- Install erosion and sediment control measures prior to any earth moving activity that will influence or affect stormwater runoff.
- Remove any item above the waterline that would interfere with the sedimentation barriers, water diversion, and clean water bypass to be installed in the channel.
- Install temporary siltation barriers, water diversion, and clean water bypass.
- Remove existing bridge.
- Segregate and stockpile the excavated stone materials, soil materials and woody debris. The stockpiled stone materials, soil materials and woody debris will be utilized in the restoration of the wetland areas to be impacted.
- Stockpile natural streambed materials to be used to restore the channel.
- Install bridge abutments, riprap, and natural streambed material inside of the new bridge.
- Install pre-manufactured bridge. Backfill and compact as required. Install fill on banks and in channel as required.
- Complete construction of the roadway and grading, as indicated in the plans. All construction must be finalized prior to removing siltation measures in the channel.
- Remove temporary siltation barriers, water diversion, and clean water bypass from the channel.
- Construct ditches and guardrail, and remove erosion control measures.
- In wetland areas to be restored, regrade area to original surface or as shown on plan with stockpiled natural materials and scarify surface to prepare for seeding.
- Seed, fertilize and mulch disturbed or filled upland areas with local conservation mix or equivalent.
- Once all contributing, upslope areas have been permanently stabilized and vegetated, remove trapped sediment from behind all silt fence, hay bales and any other temporary sediment control devices. Remove all temporary sediment control devices.

Sheet Index

Number	Sheet	Sheet Name	Latest Issue
1.	W0.01	Environmental Resource Notes	12/03/2024
2.	W1.11	Langdon Brook Plan & Profile	12/03/2024
3.	W1.12	Tributary Plan & Profile	12/03/2024
4.	W1.21	Langdon Brook Erosion & Sediment Control Plan	12/03/2024
5.	W1.22	Tributary Erosion & Sediment Control Plan	12/03/2024
6.	W3.01	Typical Channel Sections	12/03/2024
7.	W3.11	Langdon Brook Channel Sections	12/03/2024
8.	W3.12	Tributary Channel Sections	12/03/2024
9.	W5.11	Erosion & Sediment Control Details	12/03/2024

Legend

	Culvert
	Existing major contour
	Existing minor contour
	Proposed major contour
	Proposed minor contour
	Water diversion structure
	Silt fence
	Existing vegetation line
	Proposed vegetation line
	Delineated wetland
	Wetland classification
	Edge of gravel
	Edge of pavement
	Right-of-way/property line
	Erosion control matting
	Compost socks with live staking
	Proposed 1% AEP Flood Elevation

General Notes		
		
		
		
		
No.	Revision/Issue	Date

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE




R-9

Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District

	HEB Engineers, Inc. PO Box 440, 2605 White Mountain Hwy. North Conway, NH 03860 www.hebenengineers.com Office: (603) 356-6936
---	--

Drawing Title
Environmental Resource Notes

Designed/Drawn COB	Project 2023-004
Checked JKM	Drawing No. W0.01
CAD File No. -	
Date 12/03/2024	
Scale N/A	



Langdon Brook Plan
Scale: 1" = 10'

No.	Revision/Issue	Date
4		
3		
2		
1		

General Notes

Hydraulic Data	
Drainage Area	0.99 mi ²
Design Flood Discharge - Inlet (100 yr.)	732 CFS
Design Flood Elevation - Inlet (100 yr.)	826.92 ft
Design Flood Velocity (100 yr.)	4.51 FPS
Bridge Full Waterway Opening Perpendicular to River	480 ft ²

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE




R-9

Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District

HEB ENGINEERS


HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebenengineers.com
Office: (603) 356-6936

Drawing Title
Langdon Brook Plan and Profile



Langdon Brook Profile
Scale:
Horizontal: 1"=10'
Vertical: 1"=10'

Designed/Drawn	COB	Project	2023-004
Checked	JKM	Drawing No.	W1.11
CAD File No.	-		
Date	12/03/2024		
Scale	1"=10'		



Tributary Plan
Scale: 1" = 10'

General Notes		
4		
3		
2		
1		
No.	Revision/Issue	Date

Hydraulic Data	
Drainage Area	0.59 mi ²
Design Flood Discharge - Inlet (100 yr.)	374 CFS
Design Flood Elevation - Inlet (100 yr.)	831.54 ft
Design Flood Velocity (100 yr.)	3.62 FPS
Bridge Full Waterway Opening Perpendicular to River	217 ft ²

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE


R-9

Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District

HEB ENGINEERS HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebenengineers.com
Office: (603) 356-6936

Drawing Title
Tributary Plan and Profile

Designed/Drawn	COB	Project	2023-004
Checked	JKM	Drawing No.	
CAD File No.	-	W1.12	
Date	12/03/2024		
Scale	1"=10'		



Unnamed Tributary Profile
Scale:
Horizontal: 1"=10'
Vertical: 1"=10'

P:\Users\j2023\OneDrive\Documents\Projects\Corridor 19 Bridges\Drawings\W1.12\Tributary Plan.dwg, W1.12, 12/03/2024, 10:12:59 AM, j2023

Wetland Impacts Legend

- Permanent Wetland Impacts
- Temporary Wetland Impacts
- Stream Channel Impacts
- Stream Bank Impacts
- Wetland Designation Number and Location

Wetland Classification Notes

R2UB1F	1	Riverine, Upper Perennial, Unconsolidated Bottom, Cobble-Gravel, Semipermanently Flooded
PFO4E	2	Palustrine, Forested, Needle-Leaved Evergreen, Seasonally Flooded/Saturated

Wetland Impact Summary

WETLAND NUMBER	WETLAND CLASSIFICATION	LOCATION	AREA IMPACTS			
			PERMANENT SF	TEMPORARY SF	PERMANENT LF	TEMPORARY LF
1	R2UB1F	A	130	55	0	0
2	PFO4E	B	205	55	0	0
2	PFO4E	C	335	60	0	0
1	R2UB1F	D	165	60	0	0
TOTAL			835	230	0	0

Permanent Impacts: 835 SF
 Temporary Impacts: 0 SF
 Total Impacts: 835 SF

General Notes

4		
3		
2		
1		
No.	Revision/Issue	Date

U.S. DEPARTMENT OF AGRICULTURE
 FOREST SERVICE


R-9

Corridor 19 Bridges
 over Langdon Brook & Unnamed Tributary
 White Mountain National Forest
 Saco Ranger District

HEB ENGINEERS
 HEB Engineers, Inc.
 PO Box 440, 2605 White Mountain Hwy.
 North Conway, NH 03860
 www.hebengineers.com
 Office: (603) 356-6936

Drawing Title
Langdon Brook Erosion & Sediment Control Plan

Designed/Drawn	COB	Project	2023-004
Checked	JKM	Drawing No.	W1.21
CAD File No.	-		
Date	12/03/2024		
Scale	1"=10'		



P:\Jobs\2023\2023-004\W1.21\Drawings\Sheet\W1.21.dwg, W1.21, 12/03/2024, 10:13:11 AM, jbradford

Wetland Impacts Legend

- Permanent Wetland Impacts
- Temporary Wetland Impacts
- Stream Channel Impacts
- Stream Bank Impacts
- Wetland Designation Number and Location


Wetland Classification Notes

R2UB1F	1	Riverine, Upper Perennial, Unconsolidated Bottom, Cobble-Gravel, Semipermanently Flooded
PFO4E	2	Palustrine, Forested, Needle-Leaved Evergreen, Seasonally Flooded/Saturated

Wetland Impact Summary

WETLAND NUMBER	WETLAND CLASSIFICATION	LOCATION	AREA IMPACTS			
			SF	LF	SF	LF
1	R2UB1F	E	40	45	0	0
2	PFO4E	F	240	45	0	0
2	P404E	G	170	40	0	0
1	R2UB1F	H	50	40	0	0
TOTAL			500	170	0	0

Permanent Impacts: 500 SF
 Temporary Impacts: 0 SF
 Total Impacts: 500 SF



General Notes

4		
3		
2		
1		
No.	Revision/Issue	Date

U.S. DEPARTMENT OF AGRICULTURE
 FOREST SERVICE


R-9

Corridor 19 Bridges
 over Langdon Brook & Unnamed Tributary
 White Mountain National Forest
 Saco Ranger District

HEB ENGINEERS
 HEB Engineers, Inc.
 PO Box 440, 2605 White Mountain Hwy.
 North Conway, NH 03860
 www.hebengineers.com
 Office: (603) 356-6936

Drawing Title
Tributary Erosion & Sediment Control Plan

Designed/Drawn	COB	Project	2023-004
Checked	JKM	Drawing No.	W1.22
CAD File No.	-		
Date	12/03/2024		
Scale	1"=10'		



Typical Channel Section
Scale: 1" = 1'-0"

General Notes

4		
3		
2		
1		
No.	Revision/Issue	Date

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE



R-9











Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District

HEB ENGINEERS | HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebengineers.com
Office (603) 356-6936

Drawing Title
Typical Channel Sections

Designed/Drawn COB	Project 2023-004
Checked JKM	Drawing No.
CAD File No. -	W3.01
Date 12/03/2024	
Scale 1" = 1'-0"	

P:\Users\jacob@heb.com\OneDrive\Documents\Projects\Corridor 19 Bridges\Drawings\W3.01 Typical Channel Section.dwg, 12/03/2024 10:13:33 AM, jacob@heb.com



No.	Revision/Issue	Date
4		
3		
2		
1		

U.S. DEPARTMENT OF AGRICULTURE
 FOREST SERVICE

R-9


Corridor 19 Bridges
 over Langdon Brook & Unnamed Tributary
 White Mountain National Forest
 Saco Ranger District


HEB ENGINEERS
HEB Engineers, Inc.
 PO Box 440, 2605 White Mountain Hwy.
 North Conway, NH 03860
 www.hebengineers.com
 Office: (603) 356-8936

Drawing Title
Langdon Brook Channel Sections


Designed/Drawn	COB	Project	2023-004
Checked	JKM	Drawing No.	W3.11
CAD File No.	-		
Date	12/03/2024		
Scale	1" = 10'		

P:\Users\j2023\OneDrive\Documents\2023-04\W3.11\Drawings\Langdon Brook Channel Sections\W3.11_12/03/2024.dwg, W3.11, 12/03/2024, 10:13:44 AM, j2023




- NOTES:**
- IF PONDING IS ANTICIPATED OR OCCURS, DOUBLE THE NUMBER OF STAKES FOR SUPPORT.
 - SILT FENCE SHALL NOT BE USED IN CONCENTRATED FLOW AREAS.
 - SEDIMENT DEPOSITS SHALL BE INSPECTED AFTER EVERY STORM EVENT AND REMOVED WHEN DEPOSITS REACH APPROXIMATELY 1/2 THE HEIGHT OF THE SILT FENCE, OR WHEN "BULGES" DEVELOP IN THE SILT FENCE.



Silt Fence Installation
Scale: 1" = 1'



Temporary Water Diversion Structure
NTS



Erosion Blankets Slope Installation
NTS



- NOTES:**
- GEOTEXTILE BAG MATERIAL BASED ON PARTICLE SIZES IN PUMPED WATER, (I.E., FOR COARSE PARTICLES A WOVEN MATERIAL; FOR SILTS/CLAYS A NON-WOVEN MATERIAL).
 - DO NOT OVER PRESSURIZE BAG OR USE BEYOND CAPACITY.
 - LOCATE DISCHARGE SITE ON FLAT UPLAND AREAS AS FAR AWAY AS POSSIBLE FROM STREAMS, WETLANDS, OTHER RESOURCES AND POINTS OF CONCENTRATED FLOW.
 - DOWNGRADIENT FROM RECEIVING AREA MUST BE WELL VEGETATED OR OTHERWISE STABLE FROM EROSION, (I.E., FOREST FLOOR OR COARSE GRAVEL/STONE).
 - DISCHARGE LOCATION SHALL MEET ALL REGULATORY SETBACKS FROM WETLANDS AND OTHER WATER COURSES.
 - ALL MATERIALS, LABOR, CONSTRUCTION, MAINTENANCE AND REMOVAL OF THE SEDIMENTATION BASIN, AND RESTORATION OF THE AREA SHALL BE INCLUDED IN THE PAY ITEM. DISPOSE OF FILTER BAGS WHEN FULL AND REPLACE.
 - CONTRACTOR IS RESPONSIBLE FOR SIZING OF THE SEDIMENTATION BASIN. THE SEDIMENTATION BASIN SHALL HAVE SUFFICIENT CAPACITY TO FILTER PUMPED WATER THROUGH THE FILTER BAG, FILTER FABRIC, AND HAYBALES. A LARGER SEDIMENTATION BASIN OR ADDITIONAL SEDIMENTATION BASINS SHALL BE NECESSARY IF THE SEDIMENTATION BASIN IS OVERFLOWING OR OTHERWISE INCAPABLE OF FILTERING ALL PUMPED WATER. ADDITIONAL SEDIMENTATION BASINS SHALL BE INCLUDED IN THE PAY ITEM.
 - DETAILS SHOWN ARE TYPICAL FOR ALL SEDIMENTATION BASINS USED THROUGHOUT THE DURATION OF CONSTRUCTION.

Sedimentation Basin Details
NTS

4		
3		
2		
1		
No.	Revision/Issue	Date

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE

R-9

Corridor 19 Bridges
over Langdon Brook & Unnamed Tributary
White Mountain National Forest
Saco Ranger District

HEB ENGINEERS | HEB Engineers, Inc.
PO Box 440, 2605 White Mountain Hwy.
North Conway, NH 03860
www.hebengineers.com
Office (603) 356-6936

Drawing Title
Erosion & Sediment Control Details

Designed/Drawn	COB	Project	2023-004
Checked	JKM	Drawing No.	W5.11
CAD File No.	-		
Date	12/03/2024		
Scale	As Noted		